





SECtop SLC

ONE-PART SELF-LEVELLING CEMENT BASED FLOORING COMPOUND

DESCRIPTION

SpECtop SLC is a one-part self-levelling product consisting of specially selected cements, graded sands and plasticisers.

TYPICAL USES

SpECtop SLC is a very low emission floor levelling compound for producing smooth and levelled substrates for a wide range of floor finishes including mineral screeds, concrete, tiles and slabs, natural stones and terrazzo.

Note: **SpECtop SLC** to be used in dry areas only. Do not use as a screed or wearing surface and on mastic asphalt screeds.

ADVANTAGES

- Self-levelling and pumpable
- Good strength values

TECHNICAL DATA

Colour	Grey powder
Working time	Approx 20 minutes
Foot traffic	Overnight
Ready for covering	After 24 hours up to
	3mm layer thickness
	After 48 - 72 hours
	above 3mm layers
	thickness
Water content	25%
Flow table spread	270mm
Flexural strength of	
hardened mortars	5.5 N/mm²
Compressive strengh of	
hardened mortars	22.69 N/mm ²
Typical thickness	From 0.5 to 20mm in
	one single application

APPLICATION

Surface preparation

It is essential that adequate preparation is carried

out prior to the application of **SpECtop SLC**. Surface should be clean, free from structural defects, firm, permanently dry, and free of release agents. Light sweep blasting is recommended to ensure the removal of all laitance, grease and oil. Always grind calcium sulphate screeds and vacuum clean.

Priming

Primer is not required generally for a smooth, sound concrete surfaces. For extremely porous substrates use one coat of **SpECtop SLC Primer** at about 100µm wft and allow it to dry for at least 1 - 2 hours prior to the application of **SpECtop SLC**.

Mixing

SpECtop SLC is supplied as a one-part floor levelling compound.



The specified water quantity should be measured in an accurately graduated vessel and added to the mixer. The bagged powder is then added slowly whilst mixing

using a slow speed heavy duty drill fitted with a suitable mixing paddle (**SpEC Technical Department** can advise). Mix for 2 - 4 minutes.

The recommended water used per 25kg bag is 6.25 litres.

Do not mix with other levelling compounds

Application

Pour the mixed product onto the substrate and spread using a smoothing trowel or spreader. On non-absorbent mineral substrates a minimum layer thickness of 2mm must be applied. Protect the freshly applied compound from direct sunlight and droughts. Do not use in wet or outdoor areas.

ENGINEERED SOLUTIONS

EQUIPMENT CLEANING

All equipments may be cleaned with water after use.

APPLICATION T	EMPERATURE	RANGE
----------------------	------------	-------

Minimum	15°C
Maximum	25°C

PACKAGING & YIELD

SpECtop SLC is s supplied in 25kg bags with a coverage rate of 1.5 kg/m²/1mm layer thickness.

SpECtop SLC Primer is supplied in 5 and 20 litre packs with a coverage rate of 7 - 10 m²/litre.

STORAGE & SHELF LIFE

When stored in a cool environment, in original unopened containers, the material has a shelf life of **12** months.

HEALTH & SAFETY

The product is non-toxic but is mildly alkaline. Gloves should be worn during use. Splashes to the skin should be washed with clean water. Accidents splashes to the eyes should be washed with water but should prolonged irritation occur, medical advice should be sought.

FLAMMABILITY

SpECtop SLC and **SpECtop SLC Primer** are non-flammable.

Issue 2: 01/2017

QA-054

Whilst the information and/or specifications given are, to the best of our knowledge, true and accurate, no warranty is given or implied in connection with any recommendations or suggestions made by us, our representatives, agents or distributors as the conditions of use and labour involved are beyond our control.

If it is proven that the product does not perform as described in our TDS, SpEC's liability extends solely to the free replacement of product, once the claim has been accepted after due investigation by SpEC. SpEC will not entertain any claims involving any form of consequential costs or damages such as shipping costs, custom duties, damages to third parties, damages to structures, penalties from delay of a project or any other form of consequential damage.